Constructed and restored wetlands' relationship to stream restoration using natural channel design

Upper Peninsula Power Company Dead River Recovery, Marquette County, Michigan

S. Paige Baker, PE, MLE Stantec, Charlotte, NC

Sean D. Collins, PE, MLE Stantec, Charlotte, NC

Charles L. Wolverton, PWS King & MacGregor Environmental, Inc., Traverse City, MI

Stantec

November 18, 2014



Background **2** Post-construction stream **3** Post Construction wetlands 4 Wetland monitoring **5** Conclusions









2003 Dead River Flood

- May 14, 5 pm Dike at Silver Lake breaks
- An estimated 8 billion gallons of water released into the river





Human Toll

- 2300 people evacuated
- 3 dams damaged, 2 dams failed
- 9 bridges damaged or destroyed
- 1 power plant damaged
- 2 parks and 3 public access sites damaged
- Homes and camps flooded
- 14 businesses impacted, including Northern Michigan University





Environmental Toll

- River channel
 realignments
- Soil and vegetation loss
- Sediment deposition
- Debris
- Sheen of undetermined origin at City of Marquette's Upper Harbor

















Dead River Recovery Project

- Remove debris
- Create stable river
 alignment
- Prevent erosion and sedimentation
- Recover wetlands
- Replant vegetation



Design Goals

 Recover natural functions in corridor

River

 Design for valley type, slope

Wetlands

• Situate adjacent to stream on floodplain or terrace as appropriate





Confined channel







Unconfined channel





2 Post construction stream



















Post construction wetlands













4 Wetlands monitoring



Monitoring methods

- Vegetation
 - Trees and shrubs
 - Herbaceous
- Hydrology



Monitoring methods

- Vegetation
 - Trees and shrubs
 - Herbaceous
- Hydrology



Monitoring setup

- 4 piezometers were installed in project wetlands, 1 piezometer was installed in a reference wetland
- Measure near surface water table 4 times per day





Equipment setup

- Piezometers:
 - 2" diameter PVC, 28" long with a slotted point and locked cap
 - Installed by hand, bentonite placed around the casing
- The data loggers:
 - Hobo® brand, suspended in the piezometer casing by a stainless steel cable attached to a steel washer





Performance standard

- The performance standard for wetland hydrology includes:
 - Saturation in the root zone (i.e. upper 12" of the soil column) or
 - Inundation for minimum of 12.5% of the growing season
- In Marquette County growing season is 146 days; wetland hydrology must be present a minimum of 18 days.





Monitoring results

- Launched on May 24 (three project sites and reference wetland) and June 27 (additional project site)
- Shut down August 14 to prevent winter damage





Reference wetland results

At or above 12" bgs until shutdown





> Standard



Confined channel #1 results

At or above 12" bgs until July 28 (38 days)





> Standard



Confined channel #2 results

At or above 12" bgs until shutdown





> Standard



Unconfined channel #1 results

At or above 12" bgs until June 6, very close until July 10





< Standard



Unconfined channel #2 results

Wetland completed June 27; at or above 12" bgs until June 30, at 13.7" bgs until July 8





Incomplete



Confined channel > Standard-all 5 years





Unconfined channel < Standard-years 1-3 > Standard-years 4&5





Conclusions



Conclusions

Confined valleys

- Wetlands in confined valleys met standard immediately-receiving groundwater from adjacent terrace scarps.
 - Inlet control works not necessary.
 - Smaller area available for wetlands; do not neglect opportunities to include wetlands in narrow valleys.

Unconfined valleys

- Wetlands in unconfined valleys met standard within monitoring timeframe-required a longer period for groundwater levels to adjust between stream/wetland.
 - Inlet control works may be necessary.
 - Larger areas available for wetlands.



Questions?

